Comparative Statement

BBMP/2018-19/OW/WORK_INDENT34172

Improvements to roads and drains at Railway mens layout, in Ward No.06 Thanisandra

SNo	Item Name	Unit	Estimate Quantity	Estimate Rate	Total Amount	P Hemanth (SOORYA CREATERS)		K RAMACHANDRA RAJU (RR Constructions)	
						Quoted Rate	Total Amount	Quoted Rate	Total Amount
1	Clearing and grubbing road land including uprooting rank vegetation, grass, brush, shrubs, saplings and trees of girth upto 300mm, by manual means, in area of Thorney jungle, removal of stumps, disposal of unserviceable materials, stacking of serviceable materials labour charges complete as per specifications.	Sqm	4087.20	10.60	43324.32	11.45	46798.44	11.70	47820.24
2	Removing and refixing stone slabs of drains and pointing in CM (1:3)	Sqm	3576.30	111.30	398042.19	120.20	429871.26	122.50	438096.75
3	Providing granite slabs of selected quality roughly dressed havinf a size of 7.5 cms thick and fixed in cement mortar (1:6) including fixing curing ete., complete.	Sqm	1778.70	742.00	1319795.40	801.36	1425379.03	816.20	1451774.94
4	Earth work excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface levelled and sides neately dressed, the disposed earth to be levelled neatly after breaking of clods complete as per specification.	Cum	3475.60	252.49	877554.24	272.69	947761.36	277.75	965347.90
5	Providing and laying Plain cement concrete of mix 1:3:6 with OPC @ 220kgs, with crushed 40mm and down size graded granite metal coarse aggregates @0.89cum and fine aggregates @ 0.46cum, in foundation mechanically mixed, placed in foundation and compacted by vibration including curing for 14 days including cost of all materials, labour, HOM curing, form works, scaffolding and centering complete as per specifications.	Cum	426.79	5421.90	2314012.70	5855.65	2499132.86	5965.00	2545802.35
6	Providing and constructing load bearing wall with having block density not less than 1800 kg/m3 and having a minimum average compressive strength 5.00 N/mm2 confirming to IS 2185 (Part 1):2005 and constructed with CM 1:4 , as per IS 2572:2005 including cost of all materials labour charegs, scaffolding, curing, hire charges of machineries etc., complete as per specifications. KBS No.5.4 .-do- solid concrete blocks of size 400x150x200 mm	Sqm	2856.00	1010.18	2885074.08	1090.99	3115867.44	1112.00	3175872.00

SNo	Item Name	Unit	Estimate Quantity	Estimate Rate	Total Amount	P Hemanth (SOORYA CREATERS)		K RAMACHANDRA RAJU (RR Constructions) 61	
						Quoted Rate	Total Amount	Quoted Rate	Total Amount
7	Providing and laying in position plain cement concrete of mix 1:2:4 with cement @ 240kgs, with 20mm and down size graded granite metal coarse aggregates @ 0.878 cum and fine aggregates @ 0.459 cum, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications.	Cum	163.20	5599.98	913916.74	6047.98	987030.34	6159.97	1005307.10
8	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for foundations, footings, bases of columns for mass concrete including cost of all materials, labour complete as per specifications.	Sqm	93.50	273.48	25570.38	295.36	27616.16	300.00	28050.00
9	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for vertical surfaces such as walls at any thickness, including attached pilasters, buttresses, plinth and string courses cost of all materials, labour complete as per specifications.	Sqm	523.60	379.48	198695.73	409.84	214592.22	417.28	218487.81
10	Providing and laying cement concrete using 20mm and downsize granite coarse aggregates and fine aggregates of ready mixed concrete (RMC) for RCC works laid in 15cms thick layers and well compacted vibrating, curing, finishing with necessary cement mortar, with all lead and lifts etc., complete (exclusive of cpost of steel and fabricaton charges) Ready Mixed Cement Concrete M 20 for Raft foundation, Column, Footing, main and secondary beams.	Cum	116.88	5770.64	674472.40	6232.29	728430.06	6348.00	741954.24
11	Providing TMT steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, palcing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining memebrs wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications.	MT	9.35	75223.96	703344.03	81241.88	759611.58	82747.00	773684.45
12	Providing and fixing RCC Precast cover slab of 100mm thick for drain in cement concrete M20 using graded granite jelly 20mm and down size with steel reinforcement, including form work, lift charges, curing and concrete finished surfaces on both sides etc, complete and as per drawing and the directions of Engineer in-charge.	Sqm	3213.00	2337.00	7508781.00	2523.96	8109483.48	2571.00	8260623.00

SNo	Item Name	Unit	Estimate Quantity	Estimate Rate	Total Amount	P Hemanth (SOORYA CREATERS)		K RAMACHANDRA RAJU (RR Constructions) 60	
						Quoted Rate	Total Amount	Quoted Rate	Total Amount
13	Providing and fixing RCC Precast cover slab of 250mm thick for drain in cement concrete M20 using graded granite jelly 20mm and down size with steel reinforcement, including form work, lift charges, curing and concrete finished surfaces on both sides etc, complete and as per drawing and the directions of Engineer in-charge.	Sqm	224.40	5900.00	1323960.00	6372.00	1429876.80	6490.00	1456356.00
14	Cement concrete pavement.Construction of un-reinforced plain cement concrete pavement, thickness as per design, over a prepared sub base with OPC cement or any other type as per clause 1051.2.2 design mix M20/M30 , with 25mm and down size graded granite metal coarse aggregates and fine aggregtes , with superplastisiser @3lts confirming to IS9103-1999 Reaffirmed-2008 , mixed in a concrete mixer of not less than 0.6 cum capacity and appropriate weigh batcher as per approved mix design, laid in approved fixed side form work (steel channel, laying and fixing of 125 micron thick polythene film, wedges, steel plates including levelling the form work as per drawing). Spreading the concrete with shovels, rackers compacted using needle, screed and plate vibrator and finished in a continuous operation including provision of contraction, expansion, construction and longitudinal joints including groove cutting charges, joint filler, separation membrane, selant primer, joint sealant, admixtures as approved, curing compound, finishing to lines and grades as per drawing complete as per specifications. - M20 (at 300Kg per cum coarse aggregate @ 0.64cum and fine aggregate @ 0.43cum)	Cum	151.65	5128.28	777703.66	5538.54	839919.59	5642.00	855609.30
15	Vaccum de-watering with vaccum pump and suction mat and compaction with skin floater clubbed with floating disc including cost of generator, HOM of machinery, Screed Vibratory, Power Floater, blade and disc etc., with all lead and lift.	Sqm	1011.00	72.08	72872.88	77.85	78706.35	79.20	80071.20
16	Providing and fixing pre cast solid cement concrete kerb stones made out of CC 1:2:4 with top and bottom width 114 and 165 mm respectively, 400mm high and 450mm in length finished with CM 1:3 plastering and finishing cutting including formwork, curing, including cost of materials, labour charges of machinery, loading and unloading, lead and lift, transportation ete.,complete.	m	7932.00	432.48	3430431.36	467.08	3704878.56	476.00	3775632.00

SNo	Item Name	Unit	Estimate Quantity	Estimate Rate	Total Amount	P Hemanth (SOORYA CREATERS)		K RAMACHANDRA RAJU (RR Constructions)	
						Quoted Rate	Total Amount	Quoted Rate	Total Amount
17	Painting two coats after filling the surface with synthetic enamel paint in approved shades on new plastered concrete surfaces, with materials, labour complete as per specifications.	Sqm	1249.50	84.80	105957.60	91.58	114429.21	93.28	116553.36
18	Excavation for roadwork in soil with hydraulic excavator of 0.90 cum bucket capacity including cutting and loading in tippers, trimming bottom and side slopes, in accordance with requirements of lines, grades and cross sections, and transporting to embankment location and complete as per specifications.	Cum	252.75	151.66	38332.07	163.79	41397.92	167.00	42209.25
19	Providing, laying, spreading and compacting graded stone aggregate to wet mix macadam specification including premixing the Material with water at OMC in mechaniqal mix plant carriage ' of mixed Material by tipper to site, laying in uniform layers with paver in sub-base/ base course on well prepared surface and compacting with vibratory roller to achieve the desired density.complete as per specifications.	Cum	151.65	2001.28	303494.11	2161.38	327773.28	2202.00	333933.30
20	Earth work excavation for foundation of buildings, culverts, water supply, sanitary lines and electrical conduits either in pits or in trenches, 1.5m and above in width, in ordinary soil, exceeding 1.5m in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with all lead upto 50m after breaking of clods complete as per specifications.	Cum	268.80	256.47	68939.14	276.99	74454.91	282.00	75801.60
21	Providing and fixing to wall, ceiling and floor unplasticised PVC pipes 10.00 kgf/sq.cm working pressure chemp plast / Wavin or equivalent make with pipe fittings, wall clips, making good the wall, ceiling and floor, including cost of all materials,with 160mm outer dia.	Rmtr	1280.00	1327.12	1698713.60	1433.29	1834611.20	1460.00	1868800.00
22	Providing and filling sand in foundation upto plinth to required depth for sub soil treatment including watering ramming with all lead and lift complete as per specifications.	Cum	210.80	2183.60	460302.88	2358.29	497127.53	2402.00	506341.60
23	Refilling available earth around pipe lines, cables in layers not exceeding 20cms in depth, compacting each deposited layer by ramming after watering with lead upto 50m. and lift upto 1.5 m. including cost of all labour complete as per specifications.	Cum	115.20	128.26	14775.55	138.52	15957.50	142.00	16358.40

SNo	Item Name	Unit	Estimate Quantity	Estimate Rate	Total Amount	P Hemanth (SOORYA CREATERS)		K RAMACHANDRA RAJU (RR Constructions)	
						Quoted Rate	Total Amount	Quoted Rate	Total Amount
24	Providing and fixing in trenches galvanised / mild steel tubes (medium grade) 50mm dia nominal bore with all fittings (earth work in trenches to be measured and paid for separately) including cost of all materials, labour charges, HOM of equipments and testing complete as per specifications.	Rmtr	177.60	411.28	73043.33	444.18	78886.37	453.00	80452.80
	Total Summary Amount				26231109.38		28329593.46		28860939.59
	% against Estimated Rate (SR 2018-19)						8.00		10.03
	Total Bid Amount					28329593.46 (L1)		28860939.59 (L2)	

Executive Engineer
Project Division
Yelahanka Zone

28/2/19